



MOCON Laboratory

7500 Mendelssohn Ave. N | Minneapolis, MN 55428 | USA

## ASTM F2622 Oxygen Package Transmission Rate Results Report

MOCON Job Number 448331-1

PO#: 21304

Time's Up DBA H&H Enterprises

Attn: Monique Favreau

6355 Sunset Corp Dr., Las Vegas, NV 89120

### Test Conditions:

Test Gas	Oxygen	Test Temperature	23.0 °C	73.4 °F
Test Gas Concentration	100% O <sub>2</sub>	Carrier Gas	98% N <sub>2</sub> , 2% H <sub>2</sub>	
Test Gas Humidity	0% RH	Carrier Gas Humidity	0% RH	
Test Gas Pressure	760 mmHg			

### Test Results:

Sample Identification	Mocon ID	Oxygen Transmission Rate cc/ (package·day)	Steady State or Test Duration*
*CHT2 Container	9467.001	233	Steady State
*C9T2 Container	9467.002	71.2	Steady State
*H9T2 Container	9467.003	127	Steady State
F2T2 Container	9467.005	4.97	Steady State

Note: Above sample was analyzed on an Oxtran 2/10 Oxygen Permeability Instrument. \*The maximum test duration will be 120 hours, unless specifically quoted for additional testing time. The results relate only to the specific items tested.

Remarks: \*Samples Analyzed with room air (20.9% oxygen) and normalized to 100% oxygen values.

This information represents our best judgement based on work done, but the company (MOCON) assumes no liability whatsoever in connection with the use of information or findings contained herein. This report shall not be reproduced except in full without written approval of the company (MOCON). Any deviations from, additions to, or exclusions from the test method shall be noted in the remarks.

End of Report





MOCON Laboratory

7500 Mendelssohn Ave. N | Minneapolis, MN 55428 | USA

## ASTM F2622 Oxygen Package Transmission Rate Results Report

MOCON Job Number 448331-1

PO#: 21304

Date: 1/7/2019

Test Operator: CSkagerberg  
Carrie Skagerberg

Date: 1/7/19

Authorized by: H. Immel Date: 1/7/19  
Howard Immel, Standard Lab Supervisor

This information represents our best judgement based on work done, but the company (MOCON) assumes no liability whatsoever in connection with the use of information or findings contained herein. This report shall not be reproduced except in full without written approval of the company (MOCON). Any deviations from, additions to, or exclusions from the test method shall be noted in the remarks.

End of Report





MOCON Laboratory

7500 Mendelssohn Ave. N | Minneapolis, MN 55428 | USA



## ASTM F1307 Oxygen Package Transmission Rate Results Report

MOCON Job Number 448331-1

PO#: 21304

Time's Up DBA H&H Enterprises

Attn: Monique Favreau

6355 Sunset Corp Dr., Las Vegas, NV 89120

### Test Conditions:

Test Conditions:				
Test Gas	Oxygen	Test Temperature	23.0 °C	73.4 °F
Test Gas Concentration	100% O <sub>2</sub>	Carrier Gas	98% N <sub>2</sub> , 2% H <sub>2</sub>	
Test Gas Humidity	0% RH	Carrier Gas Humidity	0% RH	
Test Gas Pressure	760 mmHg			

### Test Results:

Sample Identification	Mocon ID	Oxygen Transmission Rate cc / (package·day)	Steady State or Test Duration*
W2T2 Container	9467.004	3.50	Steady State

Note: Above sample was analyzed on an Oxtran 2/21 Oxygen Permeability Instrument, following the testing procedure written within QMS 504-003. \*If Steady State has not been reached, then the transient data point (normally at 120 hours unless additional time has been purchased) will be reported. The results relate only to the specific items tested.

Remarks: Samples Analyzed with room air (20.9% oxygen) and normalized to 100% oxygen values.

Date: 1/7/2019

Test Operator: CSK  
Carrie Skagerberg

Date: 1/7/19

Authorized by: Howard  
Howard Immel, Standard Lab Supervisor

Date: 1/7/19

This information represents our best judgement based on work done, but the company (MOCON) assumes no liability whatsoever in connection with the use of information or findings contained herein. This report shall not be reproduced except in full without written approval of the company (MOCON). Any deviations from, additions to, or exclusions from the test method shall be noted in the remarks.

End of Report





MOCON Laboratory  
7500 Mendelssohn Ave. N | Minneapolis, MN 55428 | USA

## ASTM F-3136 "Package" Oxygen Transmission Rate Results Report

MOCON Job Number 493873-1

PO#: 24791

Time's Up DBA H&H Enterprises  
Attn: Sherri Hall  
1965 E Russell Rd Ste 303, Las Vegas, NV 89119

### Test Conditions:

Test Gas	Oxygen	Test Temperature	23.0 °C	73.4 °F
Test Gas Concentration	20.9% O <sub>2</sub> (room air)	Test Gas Humidity	39% RH	

### Test Results:


Sample Identification	Mocon ID	Oxygen Transmission Rate cc /(package·day)
T4 BioNatura	11753.001	1910

Note: Sample was tested using the Mocon OpTech®-O<sub>2</sub> Model P instrument. Results reflect the oxygen transmission rate with room air (20.9% O<sub>2</sub>) exposure.

Remarks: None

Sampling: MOCON Sampled per our standard procedure

Date: 4/9/2024

Test Operator:   
Carrie Skagerberg

Date: 4/9/24

Authorized by: 

Kris Bednarchuk

Date: 4/9/24

This information represents our best judgement based on work done, but the company (MOCON) assumes no liability whatsoever in connection with the use of information or findings contained herein. This report shall not be reproduced except in full without written approval of the company (MOCON). Any deviations from, additions to, or exclusions from the test method shall be noted in the remarks.

End of Report